BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/09/2013-14, Date: 10.12.2013 **ITEM NO:12**

SCHEDULE-B

NAME OF WORK: Improvements to Road, Drain, Foot path 5th A & 4th Cross Muneshwara Nagara in Bagalagunte ward No 14

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **S G ANILKUMAR**	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-2. Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	131.4	85.0	Rupees Eighty Five Only
2	Removing B.S.Slab of drain and stacking etc., complete as per specifications.	Sqm	32.4	47.0	Rupees Forty Seven Only
3	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	48.6	3980.0	Rupees Three Thousand Nine Hundred Eighty Only
4	Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	29.4	4432.0	Rupees Four Thousand Four Hundred Thirty Two Only
5	Refixing stone slabs of drains and pointing in CM 1:3 etc., complete as per specifications.	Sqm	32.4	66.0	Rupees Sixty Six Only
6	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 thick complete as per specifications.	Sqm	118.08	325.0	Rupees Three Hundred Twenty Five Only

Signature of the Contractor

Executive Engineer

7	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	q	12.15	6845.0	Rupees Six Thousand Eight Hundred Forty Five Only
8	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading complete as per specifications.	Cum	131.4	74.0	Rupees Seventy Four Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,